

SLR BOMCO Rigs - 1,500 HP AC Drilling Rigs

RIGS: SRL-242 / SRL-243	LOCATION: South America, exact location available to qualified buyers	OBSERVATIONS	
EQUIPMENT	TECHICAL SPECIFICATIONS		
MAST	MANUFACTURER	BOMCO	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	MODEL	JJ315/45-K9	
	HEIGHT	149 ft	
	STATIC HOOK LOAD	1,000,000 lbs	
	SETBACK CAPACITY	5" DP - 19,499 ft	
		5" HWDP - 918 ft	
		6 1/2" DC - 754 ft	
9 1/2" DC - 265 ft			
STANDS	8" DC - 754 ft		
STANDS	TRIPLE		
SUBSTRUCTURE	MANUFACTURER	BOMCO	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	MODEL	JG12-005	
	STATIC HOOK LOAD	1,000,000 lbs,	
	SETBACK CAPACITY	490,000 lbs	
	FLOOR HEIGHT	29.5 ft	
	CLEAR HEIGTH	25 ft	
	DRILL FLOOR AREA	41 ft x 40.4 ft	
TYPE	Slingshot		
CROWN BLOCK	MANUFACTURER	BOMCO	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	MODEL	TC-315-10	
	RATED HOOK LOAD	1,000,000 lbs	
	WIRE ROPE OD	1 3/8"	
	PRIMARY SHEAVES	6X60"	
GUIDE SHEAVES	1x60"		
TRAVELING BLOCK	MANUFACTURER	BOMCO	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	MODEL	YC315	
	STATIC HOOK LOAD	1,000,000 lbs	
	NUMBER OF SHEAVES	6X60"	
WIRE ROPE OD	1 3/8"		
HOOK	MANUFACTURER	BOMCO	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	MODEL	DG-315	
WIRE ROPE	DEAD LOAD CAPACITY	1,000,000 lbs	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	DIAMETER	1 3/8"	
	SPECIFICATIONS	6x19" IWRC EIPS RRL	
SUPPLY REEL		7,000 ft	
	DEADLINE ANCHOR	MODEL	JZG34A
SENSOR TYPE		JZ400B	
SUITABLE WIRE OD		1 3/8"	
CALIBRATION		5/8"	
SENSOR TYPE		Tension Type Sensor	
DRAWWORKS	MANUFACTURER	BOMCO	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	MODEL	JC-40DB	
	HP RATING	1,500 HP	
	DRUM GROOVING	Lebus Grooved for 1 3/8" Drilling Line	
	MAIN BRAKE	Hydraulic Disc Brake	
	AUXILIARY BRAKE	Rgenerative Type	
	DRIVE MOTORS	Two AC Motors Explosion Proof VFD	
	DRUM SIZE	(30.15x51.57)in	
	TRANSMISSION	Direct Gear Driven	
	CROWN BLOCK SAVER	Yes (Crown Block - Rig Floor)	
TOP DRIVE	MANUFACTURER	BPM	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	MODEL	DQ50BC	
	CAPACITY	700,000 Tons	
	MOTORS	1 - Electric Baldor Reliancer - 1 VFD House ABB	
	HP RATING	400 HP, 575 VAC	
	PIPE HANDLER	Yes	
	CONTINUOUS TORQUE	29502 lbs/ft	
	INTERMITENT TORQUE	44253 lbs/ft	
	MAX RPM	180 RPM	
	WORKING PRESSURE	5,000 PSI	
	CONNECTION	4 1/2" IF	
ROTARY TABLE	MANUFACTURER	BOMCO	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	MODEL	ZP275	
	OPENING DIAMETER	37 1/2"	
	MAX STATIC LOAD	1,300,000 lbs	
	MAX ROTARY SPEED	300 RPM	
	GEAR RATIO	3.56:1	
MAX TORQUE	23868 lbs/ft		
HYDRAULIC TONGS	MANUFACTURER	Jiangsu Rutong Petro-Machinery	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	MODEL	ZQ203/125 II Drill Pipe Power Tong	
	DRILL PIPE RANGE	3 1/2" - 8"	
	MAX TORQUE	92195 lbs/ft	
	MAX HYDRAULIC WP	3,000 PSI	
MAX PNEUMATIC WP	72.5 - 145 PSI		
MUD PUMPS	MANUFACTURER	BOMCO	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	MODEL	Three(3) F-1600 Triplex Mud Pumps	
	HP RATING	1,600 HP each	
	MAX WP	5,000 PSI	
	LINERS	5" -5 1/2" - 6" - 6 1/2" - 7"	
	GEAR RATIO	4.206:1	
	STROKE LENGTH	12"	
RATED SPM	120		

SUPERCHARGING PUMPS	MOTORS	1 AC Motor 1,200 Kw	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	MANUFACTURER	Chengdu West Petroleum Equipment	
	MODEL	Three (3) XBSY - SB6x8FJ-12 1/2	
	SPEED	1750 RPM	
	HP RATING	75 HP	
	CAPACITY	200 m3/h - 735 GPM	
STANDPIPE MANIFOLD	MANUFACTURER	Jiangsu Shuangxin Equipment	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	MODEL	ZG-35	
	MAX WP	5,000 PSI	
	DIMENSIONS	5" 4"	
	WORKING MEDIUM	Water, Mud, Mixture of Fluid	
	HEIGHT	Drill Floor to Gooseneck: 17.5m - 21.5 m (TDS)	
MUD PIT ROOM	MANUFACTURER	Petro HD Equipment - CNPC	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	MODEL	ZYG300/6	
	QUANTITY	Intermediate, Mixing, Reserve, Shale Shakers, Suction, Treatment, Pill	
	VOLUME	(235, 400, 400, 400, 313, 400, 100) Bls	
	GRAND TOTAL	2248 Bls	
	MUD HOPPERS	Three (3) - w/Pumps	
	MANUFACTURER	Petro HD Equipment - CNPC	

MUD AGITATORS	MODEL	ZJW7.5 - ZJW11	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	QUANTITY	Twenty-one (21) - Thirteen (13) ZJW11 - Eight (8) ZJW7.5	
	HP RATING	ZJW11 Model: 15 HP - ZJW7.5 Model: 10 HP	
	IMPELLER SPECS	ZJW11 Model: 32" Impeller ZJW7.5 Model: 28"	
	RATIO	ZJW11 Model: 36:1 ZJW7.5 Model: 35:1	
TRIP TANK	CAPACITY	63 Bls	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	SENSOR INDICATOR	Yes	
DEGASSER	MANUFACTURER	Mi-Swaco	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	MODEL	Compact Degasser	
	FLOW CAPACITY	1,000 GPM	
MUD CLEANER	MANUFACTURER	Mi-Swaco	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	MODEL	Mongoose PT Platform 2-12 Desander 8T4 Desilter	
	NUMBER OF CONES	2 Cones - 12" Desander 16 Cones - 4" Desilter	
	FLOW CAPACITY	1,000 GPM Desander 1,200 GPM Desilter	
SHALE SHAKERS	MANUFACTURER	Mi-Swaco	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	MODEL	Three (3) Mongoose Pro	
	G-FORCE	7.5 GPM	
	FLOW CAPACITY	600 GPM each	
	TYPE	Mongoose Dual Motion	
	SCREEN AREA	29.4 sq.ft	
	DECK ANGLE	-3° to +3°	
POOR BOY	MANUFACTURER	CNPC Bohai Drilling Equipment - YQF-1200	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	INTERNAL DIAMETER	48" x 20'	
	MUD INLET	5"	
	VENT LINE DIAMETER	12"	
ENGINES	MANUFACTURER	CAT	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	TYPE	Three (3) Main CAT 3512B - One (1) Auxiliary C15	
	HP RATING	1476 HP Each 3512B 430 HP C15	
	MAX RPM	1,200 Main 1,800 Auxiliary	
GENERATORS	MANUFACTURER	CAT	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	TYPE	Four (4) CAT SR4B	
	RATING MAIN GEN	1750 KVA, 1225 Kw - 60 Hertz - 3Ph - 600 VAC	
ANNULAR BOP	RATING AUX GEN	480 V, 320 EKW	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	MANUFACTURER	Shanghai Shegkai Petroleum Equipment	
	TYPE	FH35-35 Annular Preventer	
	RATED WP	5,000 PSI	
	BORE DIAMETER	13 5/8"	
	PACKING ELEMENT	Nitrile	
	TOP CONNECTION	13-5/8" -5000PSI 6BX BX160 Studded	
BOTTOM CONNECION	13-5/8" -5000PSI 6BX BX160 Studded		
DOUBLE RAM PREVENTER	MANUFACTURER	Shanghai Shegkai Petroleum Equipment	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	TYPE	Double 2FZ35-35AJ	
	RATED WP	5,000 PSI	
SINGLE RAM PREVENTER	BORE DIAMETER	13 5/8"	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	MANUFACTURER	Shanghai Shegkai Petroleum Equipment	
	TYPE	Single FZ35-35AJ	
	RATED WP	5,000 PSI	
DIVERTER	BORE DIAMETER	13 5/8"	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	MANUFACTURER	Shanghai Shegkai Petroleum Equipment	
	RATED WP	FH254-14	
	BORE DIAMETER	21 1/4"	
	RATED WP	2,000 PSI	
	PACKING ELEMENT	Nitrile	
	TOP CONNECTION	21-1/4" -2000 6B R73 Studded	
BOTTOM CONNECION	21-1/4" -2000 6B R73 Studded		
MUD CROSS	MANUFACTURER	Shanghai Shegkai Petroleum Equipment	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	BORE DIAMETER	13 5/8"	
	MAX WP	5,000 PSI	
	LATERAL CONNECTION	4 1/16" 5K PSI 6BR39 Flanged x 2 1/16" 5K PSI 6BR39 Flanged	
CHOKE MANIFOLD	MANUFACTURER	Jiangsu Jin Shi Machinery Group	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	MODEL	JGY35WD	
	RATED WP	5,000 PSI	
	VALVE SPECS	4 1/16" - 5,000 PSI	
	KILL LINE CONNECTION	2 1/16" 5,000 PSI	
	CHOKE LINE CONNECTION	4 1/16" 5,000 PSI	
ACCUMULATOR	WORKING MEDIUM	Natural Gas, Mud, All Kind of Drilling Fluids	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	MANUFACTURER	Beijing Fabrica de Maquinaria Petrolera	
	MODEL	FKQ720-6	
	RATED WP	3,000 PSI	
	TANK CAPACITY	340 Gals	
	BOTTLE CAPACITY	12 Bottles 15 Gallons each	
	ELECTRIC PUMPS	Yes - 1 Triplex	
	PNEUMATIC PUMPS	Yes - 2 - 25 HP	
SLIPS	NUMBER OF STATIONS	6	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	BYPASS VALVE	Yes	
	5" OD DRILL PIPE	Two (2) Units - W5/350T (Equivalent to VARCO SDXL)	
	3 1/2" OD DRILL PIPE	Two (2) Units - W 3 1/2/125 T (Equivalent to VARCO SDML)	
	9 1/2" DRILL COLLARS	Two (2) Units - WT8"-9 1/2"	
	8" DRILL COLLARS	Two (2) Units - WT6-3/4" - 8 1/4"	
TUBULARS	6 1/4" DRILL COLLARS	Two (2) Units WTS-1/2" - 7"	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	5" DRILL PIPE	12,000 ft 5", 19.5 lbs/ft S-135, 4-1/2" IF- W/Hardbanding & Internal Coating	
	3 1/2" DRILL PIPE	4,000 ft 3 1/2", 15.5 lbs/ft S-135, 3-1/2" IF - W/Hardbanding & Internal Coating	
	5" HWDP	125 Joints 5" HWDP - 4 1/2" IF	
	3 1/2" HWDP	21 Joints 3 1/2" HWDP - 3 1/2" IF	
	8" DRILL COLLARS	12 Joints of 8" DC - 6 5/8" REG	
	6 1/2" DRILL COLLARS	21 Joints DC - 4 1/2" IF	
	4 3/4" DRILL COLLARS	9 Joints of 4 3/4" DC - 3 1/2" IF	
5" OD DRILL PIPE	350 Ton, DD2133/3150 - Two (2) Units		
3 1/2" OD DRILL PIPE	250 Ton, DDZ101/2250 - Two (2) Units		

ELEVATORS	9 1/2" DRILL COLLARS	CD9-1/2/200T - Two (2) Units	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW (IN CONTAINER)
	8" DRILL COLLARS	CD8/200T - Two (2) Units	
	6 1/4" DRILL COLLARS	CD6-1/2/200T - Two (2) Units	
	13 3/8" CASING	13 3/8" x 350 Ton - Two (2) Units	
	9 5/8" CASING	9 5/8" x 350 Ton - Two (2) Units	
	7" CASING	7" x 150 Ton - Two (2) Units	
CASING ELEVATOR/SPIDER	5" CASING	5" x 150 Ton - Two (2) Units	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW (IN CONTAINER)
	MODEL	QD450	
	SLIPS	4 1/2" - 5" - 7" - 7 5/8" - 9 5/8" - 13 3/8" One (1) Unit	
AIR COMPRESSORS	CAPACITY	4500 KN	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	MANUFACTURER	Sullair	
	MODEL	LS-12-50HH	
	QUANTITY	Two (2)	
AUXILIARY COMPRESSOR	PRESSURE & FLOW CAP	50 HP - 198 ACFM @ 145 PSI	EQUIPMENT ON SITE, ASSEMBLY, TOTALLY NEW
	MANUFACTURER	Xi'an Hengli Compressor	
	QUANTITY	One (1)	
	PRESSURE & FLOW CAP	7 HP - 28 CFM @ 145 PSI	