

Current Location: Australia

Cantilever Mast on Dolly, Hydraulic Lift, Triple



General Description

Make	NOV
Year Built/Rebuilt	2008
Estimated Drilling Depth	18,000 ft
Estimated Rig Move Loads	80
Estimated Camp Move Loads	18
Rated HP	1500

Mast

Height	142.00 ft
Static Hook Load Capacity	750,000 lbs
Mast Racking Capacity	19,300 ft

Substructure

Style	Parallelogram
Height	25.00 ft
Clear Height	21.30 ft
Casing Capacity	750,000 lbs
Maximum Setback Load (lbs)	500,000

Drawworks

No Drawworks

Mud System

Active Mud Volume	792 bbls
Reserve Mud Volume	402 bbls
Shale Shakers	2 ea Scomi SCM-4

Top Drive / Power Swivel

No Top Drive

Mud Cleaner	N/A
Desander	Brandt 10" X 3 Cones
Desilter	Brandt 4" X 20 Cones

Centrifuge N/A

Well Control

Swivel

No Swivel

Annular 13 5/8" 5,000 psi, Spherical Bolted

Single Ram Preventer 13 5/8 10,000 psi

Choke Manifold MI Swaco 10K 4-1/16

Rotary Table

Make .NOV ZP-375

BOP closing Unit Sara Sae Type 80

Table Opening .37 1/2"

Maximum Load Rating .650 Ton

Power Generation

Engines 3 ea MTU 12V4000G73

Generators 3 ea Baylor Generation Group
S637UUT-200

SCR / VFD / DC/DC VFD Rig

Enhancements