

This is an Overview of the main components/equipment offered with this rig. Additional components can be purchased separately at additional costs. It is the Buyers Responsibility to inspect the equipment prior to purchase. No Warranties are offered, expressed, or implied, all equipment is offered in As-Is, Where-Is Condition.

## **RIG #17**

**Rated: 16,000 ft**

### **DRAWWORKS**

National 80UE w/ EDS System

### **TRAVELING BLOCK & HOOK**

Skytop 500 Ton w/ BJ 500 Ton Hook

### **TOP DRIVE**

Canrig 275 Ton 6027 AC

### **PRESSURE CONTROL**

B.O.P is NOT included

CLOSING UNIT - 160 Gallon Hydril 8 Station

CHOKE MANIFOLD - 3" 5M

### **MUD SYSTEM**

MUD PUMP #1 - Emsco FB-1600

MUD PUMP #2 - Emsco FB-1600

MUD TANKS – (2) Tanks - 1200 BBL

SHALE SHAKER – Dual NOV King Cobra

### **TUBULARS & HANDLING**

MECHANICAL ROUGHNECK – Forum WR-80

POWER CATWALK – NOT INCLUDED

DRILL PIPE – Additional Cost

DRILL COLLARS – Additional Cost

### **STORAGE CAPACITIES**

WATER TANKS - 600 BBL

### **POWER PACKAGE AND LIGHTING**

SCR - Omron PLC System w/ 3 x 3 Top Drive Feeder

ENGINES - (3) MTU V16 2000

### **MAST AND SUBSTRUCTURE**

MAST – Superior 136' w/ 600,000# GNC

SUBSTRUCTURE – Superior Box on Box 28'

HIGH DENSITY SELF MOVING PACKAGE – 135' Center of Well

### **AUXILIARY EQUIPMENT**

GAS BUSTER ATMOSPHERIC – Swaco Specifications

AIR HEATER AS NEEDED – 2.4 Million BTU

BOILER - 150 HP Williams Davis

PUSHER HOUSE - 13' X 55' Atco