

EXHIBIT "A"
RIG #2
Depth 7,000' to 10,500'

- Skytop Brewster N-42 750HP Drawworks
 - Powered by (2) D-353 Caterpillar Engines
 - (2) Quincy 325 Compressors
- 131' x 15 ½' Butler Parks
 - w/6 sheave crown cluster, 1-1/8" grooving
- 40'L x 21'W x 14'H Box on Box Substructure
 - w/matching v-door & catwalk assembly
- 20 ½" National Rotary Table
- 250T Block/Hook Combo – 1-1/8" grooving, 5 sheaves
- 300T Swivel
- Mud Pumps-
 - #1 – LZHT 1000HP TriPlex Pump Powered by C-27 Caterpillar Engine
 - #2 – LZHT 1000HP TriPlex Pump Powered by C-27 Caterpillar Engine
- Generator House- w/attached storage
 - Complete w/electrical distribution panels
 - (2) 320KW Generators powered by 3406B Caterpillar Engines
 - Curtis Toledo Screw Air Compressor
- Explosion Proof Lighting
- 15,000' Electric Over Hydraulic Survey Machine
- Satellite Automatic Driller
- Mud Pit System-
 - 600 Bbl. Mud Tanks
 - Cobra Linear Motion Shale Shaker
 - (2) Centrifugal Mud Mixing Pumps
 - Premix Tank
 - Desander
- 500 Bbl. Water Tank w/fresh water circulating system & parts house attached
- 9400 Gallon Fuel Tank w/transfer pumps
- 900 Gallon 4 Compartment Lubester
- BOP Equipment-
 - 11" x 3000# Spherical Annular BOP
 - Townsend Type 82 – 11" x 3000# Double Ram BOP
 - 11" x 3000# Mud Cross w/outlets
 - (2) 3-1/8" x 3000# Choke Valves
 - (2) 2-1/16" x 3000# Kill Valves
 - 3" x 3000# Manifold (skidded)
 - 4 Station 3000# Closing Unit w/Remote Panel (skidded)
- 10,000' 4" 14.0# S-135 Drill Pipe
- (18) 6 ¼" x 2 ¼" x 31' Drill Collars
- 40' – 4 ¼" Hex Kelly w/Drive Bushings

RIG #2

(Continued)

- Drillers Dog House – Fully Equipped w/all necessary drilling tools
- Mud House
- Change House
- Matting Boards-
 - 8' x 25' x 6"
 - 8' x 10' x 6"
- All necessary OSHA compliant safety equipment

