This is an Overview of the main components/equipment offered with this rig. Additional components can be purchased separately at additional costs. It is the Buyers Responsibility to inspect the equipment prior to purchase. No Warranties are offered, expressed, or implied, all equipment is offered in As-Is, Where-Is Condition.

RIG #32

DRAWWORKS Brewster N-95

TRAVELING BLOCK & HOOK 500 Ton National

ROTARY TABLE National 27-1/2""

TOP DRIVE Canrig 275 Ton 6027 AC

PRESSURE CONTROL

B.O.P – is NOT included CLOSING UNIT - 160 Gallon 8 Station CHOKE MANIFOLD - 3" 5M

MUD SYSTEM

MUD PUMP #1 –Emsco FB-1600T MUD PUMP #2 –Emsco FB-1600T MUD TANKS – 1200 BBL SHALE SHAKER – (2) Dual NOV/Brandt Shakers DESILTER – Swaco 12 Cone DESANDER – Swaco 2 Cone

STORAGE CAPACITIES

WATER TANKS - 500 BBL

POWER PACKAGE AND LIGHTING

SCR - Omron PLC System w/ 3 x 3 Top Drive Feeder ENGINES - (3) Detroit V16 2000

MAST AND SUBSTRUCTURE

MAST – Superior 142' w/768,000# GNC SUBSTRUCTURE – Superior Box on Box 20'Hx36'x25' HIGH DENSITY SELF MOVING PACKAGE – 135' Center of Well

AUXILIARY EQUIPMENT

GAS BUSTER ATMOSPHERIC - Swaco Specifications BOILER - 150 HP William Davis PUSHER HOUSE - 14' X 55' Ameri-Tech

TUBULARS & HANDLING

MECHNICAL ROUGHNECK – FM-80 POWER CATWALK – Additional Cost DRILL PIPE – Additional Cost DRILL COLLARS – Additional Cost

Rated: 18,000 ft