

This is an Overview of the main components/equipment offered with this rig. Additional components can be purchased separately at additional costs. It is the Buyers Responsibility to inspect the equipment prior to purchase. No Warranties are offered, expressed, or implied, all equipment is offered in As-Is, Where-Is Condition.

RIG #16

Rated: 14,000 ft

DRAWWORKS

National 80UE

TRAVELING BLOCK & HOOK

Oilwell 350 Ton

TOP DRIVE

Canrig 275 Ton

PRESSURE CONTROL

BOP IS NOT INCLUDED

CLOSING UNIT - 210 Gallon Koomey 6 Station

CHOKE MANIFOLD - 3" 5M

MUD SYSTEM

MUD PUMP #1 - Emsco FB-1600

MUD PUMP #2 - Emsco FB-1600

MUD TANKS – (2) Tanks - 1200 BBL

SHALE SHAKER – Dual NOV King Cobra

STORAGE CAPACITIES

WATER TANKS - 400 BBL

POWER PACKAGE AND LIGHTING

SCR - Omron PLC System w/ 3 x 3 Top Drive Feeder

ENGINES - (3) Cat 3512 w/ 1205 kW Kato

MAST AND SUBSTRUCTURE

MAST – DSI 142' w/750,000# Hook

SUBSTRUCTURE – Box on Box 20' 450,000 Set Back

AUXILIARY EQUIPMENT

GAS BUSTER ATMOSPHERIC

BOILER - 150 HP

PUSHER HOUSE - 12' X 50'



PetroRigs

TUBULARS & HANDLING

MECHANICAL ROUGHNECK – Forum WR-80

This is an Overview of the main components/equipment offered with this rig. Additional components can be purchased separately at additional costs. It is the Buyers Responsibility to inspect the equipment prior to purchase. No Warranties are offered, expressed, or implied, all equipment is offered in As-Is, Where-Is Condition.

RIG #17

Rated: 16,000 ft

DRAWWORKS

National 80UE w/ EDS System

TRAVELING BLOCK & HOOK

Skytop 500 Ton w/ BJ 500 Ton Hook

TOP DRIVE

Canrig 275 Ton 6027 AC

PRESSURE CONTROL

B.O.P is NOT included

CLOSING UNIT - 160 Gallon Hydril 8 Station

CHOKE MANIFOLD - 3" 5M

MUD SYSTEM

MUD PUMP #1 - Emsco FB-1600

MUD PUMP #2 - Emsco FB-1600

MUD TANKS – (2) Tanks - 1200 BBL

SHALE SHAKER – Dual NOV King Cobra

TUBULARS & HANDLING

MECHANICAL ROUGHNECK – Forum WR-80

POWER CATWALK – NOT INCLUDED

DRILL PIPE – Additional Cost

DRILL COLLARS – Additional Cost

STORAGE CAPACITIES

WATER TANKS - 600 BBL

POWER PACKAGE AND LIGHTING

SCR - Omron PLC System w/ 3 x 3 Top Drive Feeder

ENGINES - (3) MTU V16 2000

MAST AND SUBSTRUCTURE

MAST – Superior 136' w/ 600,000# GNC

SUBSTRUCTURE – Superior Box on Box 28'

HIGH DENSITY SELF MOVING PACKAGE – 135' Center of Well

AUXILIARY EQUIPMENT

GAS BUSTER ATMOSPHERIC – Swaco Specifications

AIR HEATER AS NEEDED – 2.4 Million BTU

BOILER - 150 HP Williams Davis

PUSHER HOUSE - 13' X 55' Atco

This is an Overview of the main components/equipment offered with this rig. Additional components can be purchased separately at additional costs. It is the Buyers Responsibility to inspect the equipment prior to purchase. No Warranties are offered, expressed, or implied, all equipment is offered in As-Is, Where-Is Condition.

RIG #26

DRAWWORKS

National 80UE

TRAVELING BLOCK & HOOK

Gardner Denver 300 Ton

ROTARY TABLE

National 23"

TOP DRIVE

Canrig 275 Ton AC

PRESSURE CONTROL

B.O.P – is NOT included

CLOSING UNIT - Koomey Type 80 718 Gallon (16 Bottles)

CHOKE MANIFOLD - 3" 5M

MUD SYSTEM

MUD PUMP #1 - Emsco FB-1600

MUD PUMP #2 - Emsco FB-1600

MUD TANKS – (2) Tanks - 700 BBL

SHALE SHAKER – NOV King Cobra

STORAGE CAPACITIES

WATER TANKS - 400 BBL

POWER PACKAGE AND LIGHTING

SCR - Omron PLC System w/ 3 x 3 Top Drive Feeder

ENGINES - (3) MTU V16 2000

MAST AND SUBSTRUCTURE

MAST – National 142' w/760,000# Hook

SUBSTRUCTURE – National 21'

AUXILIARY EQUIPMENT

GAS BUSTER ATMOSPHERIC – Swaco Specifications

BOILER - 150 HP Superior

PUSHER HOUSE - 12' X 52' Altra Fab



PetroRigs

TUBULARS & HANDLING

MECHNICAL ROUGHNECK – B&V

POWER CATWALK – NOT included

DRILL PIPE – 4 1/2" Additional Cost

DRILL COLLARS – Additional Cost

This is an Overview of the main components/equipment offered with this rig. Additional components can be purchased separately at additional costs. It is the Buyers Responsibility to inspect the equipment prior to purchase. No Warranties are offered, expressed, or implied, all equipment is offered in As-Is, Where-Is Condition.

RIG #27

Rated: 16,000 ft

DRAWWORKS

Oilwell 840E

TRAVELING BLOCK & HOOK

Ideco 525

ROTARY TABLE

Ideco 27 1/2"

TOP DRIVE

Canrig 275 Ton

PRESSURE CONTROL

B.O.P – is NOT included

CLOSING UNIT - 210 Gallon Koomey 6 Station

CHOKE MANIFOLD - 3" 5M

MUD SYSTEM

MUD PUMP #1 – Continental Emsco FB-1600

MUD PUMP #2 – Continental Emsco FB-1600

MUD TANKS – (2) Tanks - 1100 BBL

SHALE SHAKER – (2) Brandt King Cobra Shakers

STORAGE CAPACITIES

WATER TANKS - 600 BBL

POWER PACKAGE AND LIGHTING

SCR - IPS PLC System w/ 3 x 3 Top Drive Feeder

ENGINES - (3) Cat 3512C 1500 kW

MAST AND SUBSTRUCTURE

MAST – Superior 142' w/768,000# GNC

SUBSTRUCTURE – Box on Box 22' Set Back

HIGH DENSITY SELF MOVING PACKAGE – 135' Center of Well

AUXILIARY EQUIPMENT

GAS BUSTER ATMOSPHERIC – Swaco Specifications

BOILER - 150 HP Superior

PUSHER HOUSE - 12' X 52' Alta-Fab



PetroRigs

TUBULARS & HANDLING

MECHNICAL ROUGHNECK – B&V

POWER CATWALK – Additional Cost

DRILL PIPE – Additional Cost

DRILL COLLARS – Additional Cost

This is an Overview of the main components/equipment offered with this rig. Additional components can be purchased separately at additional costs. It is the Buyers Responsibility to inspect the equipment prior to purchase. No Warranties are offered, expressed, or implied, all equipment is offered in As-Is, Where-Is Condition.

RIG #29

Rated: 16,000 ft

DRAWWORKS

Oilwell 860E

TRAVELING BLOCK & HOOK

Skytop Brewster 500 Ton

ROTARY TABLE

Ideco 27 1/2"

TOP DRIVE

Canrig 275 Ton 6027 AC

PRESSURE CONTROL

BOP IS NOT INCLUDED

CLOSING UNIT - 160 Gallon 6 Station

CHOKE MANIFOLD - 3" x 2" 5M

MUD SYSTEM

MUD PUMP #1 – Emsco F-1600

MUD PUMP #2 – Emsco F-1600

MUD TANKS – (2) Tanks - 1200 BBL

SHALE SHAKER – (2) Dual King Cobra Shakers

DESILTER – 12 Cone Mud Cleaner And Desander

STORAGE CAPACITIES

WATER TANKS - 700 BBL

POWER PACKAGE AND LIGHTING

SCR - Omron PLC System w/ 3 x 3 Top Drive Feeder

ENGINES - (3) Detroit V16 2000 Tier 2

MAST AND SUBSTRUCTURE

MAST – Superior 142' w/768,000# GNC

SUBSTRUCTURE – W&W Rigs Box on Box 20'x36'x25'

HIGH DENSITY SELF MOVING PACKAGE – 135' Center of Well

AUXILIARY EQUIPMENT

GAS BUSTER ATMOSPHERIC

TUBULARS & HANDLING

MECHNICAL ROUGHNECK – Forum WR-80

POWER CATWALK – Additional Cost

HYDRAULIC MOUSE HOLE

DRILLING EQUIPMENT

DATA ACQUISITION



PetroRigs

This is an Overview of the main components/equipment offered with this rig. Additional components can be purchased separately at additional costs. It is the Buyers Responsibility to inspect the equipment prior to purchase. No Warranties are offered, expressed, or implied, all equipment is offered in As-Is, Where-Is Condition.

RIG #32

Rated: 18,000 ft

DRAWWORKS

Brewster N-95

TRAVELING BLOCK & HOOK

500 Ton National

ROTARY TABLE

National 27-1/2"

TOP DRIVE

Canrig 275 Ton 6027 AC

PRESSURE CONTROL

B.O.P – is NOT included

CLOSING UNIT - 160 Gallon 8 Station

CHOKE MANIFOLD - 3" 5M

MUD SYSTEM

MUD PUMP #1 –Emsco FB-1600T

MUD PUMP #2 –Emsco FB-1600T

MUD TANKS – 1200 BBL

SHALE SHAKER – (2) Dual NOV/Brandt Shakers

DESILTER – Swaco 12 Cone

DESANDER – Swaco 2 Cone

STORAGE CAPACITIES

WATER TANKS - 500 BBL

POWER PACKAGE AND LIGHTING

SCR - Omron PLC System w/ 3 x 3 Top Drive Feeder

ENGINES - (3) Detroit V16 2000

MAST AND SUBSTRUCTURE

MAST – Superior 142' w/768,000# GNC

SUBSTRUCTURE – Superior Box on Box 20'Hx36'x25'

HIGH DENSITY SELF MOVING PACKAGE – 135' Center of Well

AUXILIARY EQUIPMENT

GAS BUSTER ATMOSPHERIC - Swaco Specifications

BOILER - 150 HP William Davis

PUSHER HOUSE - 14' X 55' Ameri-Tech

TUBULARS & HANDLING

MECHANICAL ROUGHNECK – FM-80

POWER CATWALK – Additional Cost

DRILL PIPE – Additional Cost

DRILL COLLARS – Additional Cost