

General Rig Specs

Draw Works: Crown Energy CE1000ESD

Power: 1 - GE 752 Traction Motor

Rotating System: 250 Ton AC Electric Top Drive, Hydraulic 20-1/2" Rotary Table, NOV-ST80-Gen3

Mast: Crown Telescoping Double 118' with 440,000 # SHL

Substructure: Crown 18' Telescoping Sub 440,000 # Rotary, 300,000 # Setback

Electrical Power System: 3 – Cat 3508C w/ Cat 902 KW Gens, Rig capable of running on line power.

Ross Hill 3X4 Model 1400 SCR House

Pipe Handling System: Canrig PC3000 Hydraulic Catwalk

Mud Pumps: (Pumps equipped with Premium Shur-Lock system), #1 – National 10-P-130 1300Hp, #2

– National 10-P-130 1300Hp

Power: 1 - GE 752 Traction Motor

Traveling Block: 265 Ton Ideco Block

Drill Pipe: 12,000' 4-1/2" 16.60# XH

HWDP: 24 4-1/2"

Drill Collars: 24 6-1/2" 4-1/2" XH Connections

Annular Preventer: Townsend Type 84 11" X 5,000 psi

Ram Preventer: Townsend Type 82 Double Ram 11" X 5,000 psi

Choke Manifold: 4 1/16 X 5,000 psi

Accumulator System: Advanced Pressure 5 station w/180 gal. Reservoir, Remote Panel on Top Dog House

Mud System: 750 BBL Pit System 2 – MiSwaco Mongoose Shakers, Desander - National 2 Cone

Desilter - National 16 Cone

Water Tank: 300 BBL

Diesel Tank: 12,000 Gallon

Auxiliary Equipment: Automatic driller, Benchtree, D&I MWD, Change House/ Parts House, Skidding package, Two 8000# Braden hydraulic hoist

*DRAW WORKS AND MAST ARE TRAILER MOUNTED