

RMI workover Rig Specs

Refurbished in 2010 by NOV in Victoria, Texas

Total Rig Hours up to Date of September 6, 2024 - 12,618.2 hours

Rig is equipped with Detroit 60 Series Engine & 5860 Allison Transmission 6 Speed Hi-Lo

96' Derrick Rated at 180,000# on 4 lines and 215,000# on 6 Lines

Hydro-Matic Rod Basket, 1" Swedge Drill Line, 'Bradin Winch, 40' x 4, 'Base 'Beam

4 Hydraulic Leveling Jacks, Traveling Block strung up on 4 lines tubing bells

SN 2276 - Cavins 125 ton Air Slips w/ 2 3/8", 2 7/8" and 3 1/2" Slip Segments

SN 551 • Tubing Tongs D&D 58-93-2-R with Tong Jaws for 2 3/8" & 2 7/8" tubing

Also has Air Operated Back-ups, Extra Tong & Back Up Dies

Elevators for 2 3/8" & 2 7/8" Tubing

BOP's Townsend 7 1/16 x 5-K Hydraulic Tubing and Blind Rams

Ram Rubbers & Ram Blocks for 2 3/8", 2 7/8" and 3 1/2" Rams

Extra Top Seals, Door, Gaskets & Ram Rubbers

Rod Tongs Oil Country

Rod Jaws, Elevators, Rod Transfers & Rod Wrenches for 3/4", 7/8" & 1" Rods

Rod BOP's, Work Table for Rods w/ Rod Stripper, Rod Hook

SN RS 14-037 – Pump RS-W440 Triplex Piston Pump

w/ Detroit 60 Series Diesel Engine, w/ Automatic Transmission O'Drill

SN 39663 -MCM Centrifugal Pump Model 250 Series

SN 39663 -MCM Centrifugal Pump Model 250 Series

2" Pressure Hoses w/ 602 Unions